



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
5-30-1978  
MAY 30 1978  
CONSERVATION DIVISION

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Nelson of Blue Goose Drlg. Co has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. + Sidwell

Complete Address: 205. Litwin. Bldg. Wichita Ks.

Lease Name: Mills. "G" Well No. #1.

Location: SE-SE Sec. 26 Twp. 11 Rge. 40 (E)(W)

County: Wallace Total Depth 5375 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Nelson was instructed to plug the well as follows:

Pump down Drild. stem.

70. ex. cem. 50/50 Poz. 6% Gel. @ 1700'

20 " " " " " " 300'

Build Bridge To 40'

10. ex. cem 50/50 Poz. 6% Gel. 40' to 0'

Very truly yours,

Julius Belthazar  
Conservation Division Agent