

State of Kansas



15-143-20001-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

May 30, 1979

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
6-12-1979
JUN 12 1979
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Gerritzen of Emphasis Oil Operations has this date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Terra Resources, Inc.

Complete Address: Box 839, Oklahoma City, Oklahoma

Lease Name: Buhler Well No. 1

Location: NE SE NW Sec. 16 Twp. 12 Rge. 1 (E)(W) X

County: Ottawa Total Depth 3520' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

Fill hole with mud. Pump 35 sacks cement through
drill pipe at 300'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Bridge
rathole and cement with 2 sacks cement.
8 7/8" - 320' - cement circulated

Very truly yours,

Conservation Division Agent