

Recvd
KCC 04-11-1935



:: I. W. MURFIN ::

Union National Bank Building
WICHITA, KANSAS

April 11, 1935

PLUGGING
FILE SEC. 14 T. 12 R. 13 W
BOOK PAGE 7 LIRE-8

Mr. T. A. Morgan
State Empire
Bitting Building
Wichita, Kansas

Dear Sir:

The J. Garfield Buell Company, through I. W. Murfin wishes permission through your office to plug the No. 1 Funk Well, situated in:

The Southwest Corner of Section 19,
Township 12, Range 13 West, Russell
County, Kansas.

The well at the present time has four strings of pipe in it: 12-inch, 10-inch, 8-inch and 6-inch. The 6-inch is set near the top of the silicious lime.

The method we will use in plugging this well is as follows: To dump ten sacks of cement, letting it set over night; then fill the hole with sand pumpings up considerable distance; then pull the 6, 8 and 10-inch casing, and before pulling the 12-inch, drive plug in anhydrite lime at approximately 850 feet and cement; then fill with rock and mud to surface.

Yours very truly,

J. GARFIELD BUELL COMPANY,

BY *I. W. Murfin*

IWM:BM

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss.

I, the undersigned, being first duly sworn, say that the No. 1 Funk Well has been plugged in the above manner.

Subscribed and sworn to before me, this _____ day of _____, 1935.

My Commission Expires:

Notary Public.

April 11, 1935

*W. J. ...
19-2-1935
Russell County*

J. Garfield Buell Co.
Wichita, Kansas

Att'n: Mr. I. W. Murfin

Gentlemen:

We have your letter of April 11, relative to plugging No. 1 Funk well located in SWC of Sec. 19-T12S-Range 13W, Russell County, Kansas.

You are hereby authorized to plug this well in the manner suggested in your letter, with the exception that I suggest and believe it advisable that you put some cement in above the 850 ft. level, so as to prevent any infiltration of water into the upper horizon.

Bear in mind that the new law, for which there are no rules and regulations as yet promulgated, carries a fine of \$500 and six months in prison in case of violation.

Relative to dumping the ten sacks of cement into the bottom of the hole and letting it set over night, I do not believe this is sufficient time to test the cement and request that before continuing the plugging that you put some water in the hole and see if the cement in the hole has set sufficiently to keep the water from penetrating the lower horizon.

The responsibility of the producer never ceases and he can be called upon at any time under any consideration to re-plug the well.

Yours very truly,

TAM:ap
cc-J. Garfield Buell Co.

STATE OIL SERVICE

Tulsa, Okla