

15-109-20267-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-109-20,267-00-00

SE, Sec. 4, T 11 S, R 36 WPE

2200 feet from N/S section line

600 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7506

Lease Name Kronwall Well #43-4

Operator: First Energy Corp.  
Name & Address 633 N. State Box 2066  
Jackson, Mississippi 39205

County Logan

Well Total Depth 5040 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 300'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co License Number 24

Address 617 Union Center, Wichita, Ks 67202

Company to plug at: Hour: 2:00 PM Day: 22 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO John Manders

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: Order 190 sacks 50 pos mix - 6% Gel. - 3% Gel. Cl. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 2840'

w/ 20 shs. 2nd plug C 1590' w/ 100 shs. 3rd plug C 350' w/ 40 shs.

4th plug - solid bridge of balls & plug C 40' w/ 10 shs.

Circulate 10 shs in rat hole & 10 shs in mouse hole.

Signed G. G. Schul (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:00 PM Day: 22 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 310' w/ 250 shs. cement - 2% Gel. - 3% Gel. Cl.

Ordered 190 sacks 50 pos mix - 6% Gel. - 3% Gel. Cl. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C

2840' w/ 20 shs. 2nd plug C 1590' w/ 100 shs. 3rd plug C 350' w/

40 shs. 4th plug C 40' w/ 10 shs.

Circulated 10 shs in rat hole & 10 shs in mouse hole.

Remarks: No. Druckle

RECEIVED  
STATE CORPORATION COMMISSION  
1-10-1983  
JAN 10 1983

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not) observe this plugging.

INVOICED  
DATE 1-31-83  
INV. NO. 2289-W

Signed G. G. Schul (TECHNICIAN)