

8-29

2-030943

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

15-143-20008-00-00

API NUMBER: 15-143-20,008

SE SW, SECTION 15 TOWNSHIP 12 RANGE 3W

OPERATOR LICENSE # 30434 662 FEET FROM S SECTION LINE
3314 FEET FROM E SECTION LINE

OPERATOR Morris E. Ogle
NAME & P. O. Box 992
ADDRESS Casper, WY 82601

LEASE NAME: Mildred Stanley #1
COUNTY: Ottawa
WELL TOTAL DEPTH: 3760' 122.20

PIPE: _____
SURFACE CASING: 8-5/8" @ 218' CTS

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SLD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: White & Ellis Drilling, Inc.
ADDRESS: Wichita, KS LICENSE: 5420

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 29 MONTH: 8 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Verlin Graves
COMPANY NAME: White & Ellis Drilling, Inc. PHONE: 316-321-5050

WERE: Fill hole/mud - run dp to 3733' - spot 35 sx cmt -
pull dp to 330' - spot 50 sx cmt - pull dp to 60' -
spot 25 sx cmt - pump 10 sx cmt in rat hole.

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 12:45 DAY: 29 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:
Filled hole/mud - ran drill pipe to 3733' - United
Cementing #170 spotted 35 sx cmt - pulled dp to 330' -
spotted 50 sx cmt - pulled dp to 60' - pumped 25 sx
cmt to surf - pumped 10 sx in rat hole.

REMARKS: _____

I DID NOT OBSERVE THIS PLUGGING.

Don Thompson
"Don Thompson" (AGENT)
CONSERVATION COMMISSION

FORM CP-2/3
REV. 3/90

INVOICED

DATE OCT 05 1990

INV. NO. 29526

10-1-1990
OCT 1 1990

CONSERVATION DIVISION
Wichita, Kansas

ML