

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21580-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 18-26S-33W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: STONE A Well #: 1
County: FINNEY Total Vertical Depth: 5261 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4948		WITH 2 SX CMT
SURF	8.625	1892		WITH 750 SX CMT
DVT		3218		WITH 235 SX CMT
PROD	4.5	5254	1750	WITH 435 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2009 1:00 PM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2040

Proposed Plugging Method: CIBP @ 4950' & 2 SX CMT. PLUG AT 1920' WITH 20 SX GEL & 50 SX CMT. PLUG AT 900' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

170-98

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2009 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4948' WITH 2 SX CMT. 1ST PLUG AT 1750' WITH 20 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG AT 900' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5138	5144		
5002	5008		

INVOICED
DATE 6-12-09
INV. NO. 2009061600

KANSAS CORPORATION COMMISSION

MAY 14 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

MAY - 4 2009

KCC DODGE CITY

Signed

[Signature]
(TECHNICIAN)

Form CP-27