

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21581-00-01  
Spot: NWNENW Sec/Twnshp/Rge: 18-26S-33W  
4937 feet from S Section Line, 3594 feet from E Section Line  
Lease Name: STONE SWD Well #: 3-18  
County: FINNEY Total Vertical Depth: 5300 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1915		WITH 850 SX CMT

Well Type: SWD UIC Docket No: D27537.0 Date/Time to Plug: 04/28/2009 1:00 PM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2040

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

172.25

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 04/30/2009 1:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 1370' WITH 10 BBL GEL & 200# HULLS. NO CIRCULATION. 2ND PLUG AT 1170' WITH 50 SX CMT & 175# HULLS. NO CIRCULATION. PULL TO 740' & LOAD HOLE. 3RD PLUG AT 740' WITH 50 SX CMT. FULL CIRCULATION. 4TH PLUG AT 300' WITH 40 SX CMT. PARTIAL CIRCULATION. 5TH PLUG AT 30' WITH 30 SX CMT. PARTIAL CIRCULATION. CMT FELL BACK. 4/29/09: CHECK TOC. TOC @ 300'. 4/30/09: PUMP 125 SX CMT IN 3 STAGES TO TOP WELL OFF TO 0'. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
1412	1552		

INVOICED  
DATE 6-12-09  
INV. NO. 2009061600

KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

MAY 14 2009  
RECEIVED

District: 01

RECEIVED

MAY - 5 2009

KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)

Form CF-2/3