

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PCT

API Well Number: 15-151-19031-00-00
Spot: ~~E2~~ ^{SWNE} NWNE Sec/Twnshp/Rge: 7-27S-12W
4656 feet from S Section Line, 1702 feet from E Section Line
Lease Name: ICHU Well #: 15
County: PRATT Total Vertical Depth: 4262 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3136		
SURF	8.625	425		WITH 250 SX CMT
PROD	5.5	4233	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/30/2009 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: SAND TO 2400' & 5 SX CMT. PLUG AT 1050' WITH 25 SX CMT. PERFORATE @ 430'. CIRCULATE CMT TO 0'.

138.52

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2009 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

WELL HAD BEEN SQUEEZED W/CMT. HAVE CMT FROM 535-750' IN 5 1/2"/8 5/8" ANNULUS SANDED BACK TO 2500' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. RUN 2 3/8" TBG INTO 1050' & SPOT 25 SX CMT. LAID TBG DOWN. PERFORATED @ 450'. PUMPED DOWN 5 1/2" CASING W/10 SX GEL & 175 SX CMT. CMT CIRCULATED UP 5 1/2"/8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2723	3070		

INVOICED
DATE 6-12-09
INV. NO. 2009061602

KANSAS CORPORATION COMMISSION
MAY 14 2009

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

RECEIVED

Plugged through: TBG

District: 01

Signed

Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
MAY 11 2009
KCC DODGE CITY