

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20523-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 7-23S-16W
3010 feet from S Section Line, 1314 feet from E Section Line
Lease Name: SCHARTZ A Well #: 1
County: PAWNEE Total Vertical Depth: 4196 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	329		WITH 250 SX CMT
PROD	4.5	4192	2130	WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/05/2009 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 1070' WITH 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2009 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT. TAGGED CMT @ 3800'. 1ST PLUG AT 1070' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

136.37

Perfs:

Top	Bot	Thru	Comments
4118	4130		
4109	4113		
4096	4101		

INVOICED
DATE 6-12-09
INV. NO. 2009061606

KANSAS CORPORATION COMMISSION

MAY 14 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

RECEIVED

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

MAY 11 2009

KCC DODGE CITY

Form CP-2/3