

6070219

API NUMBER 15-063-20, 805-70-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE-NE-NW, SEC. 25, T 11 S, R 26 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4950 ^{FSV} feet from SE section line

2970 ^{FEV} feet from SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5813

Lease Name Jamison "B" Well # 1

Operator: F. & M. Oil Company Inc

County Gore

Name & Address 422 Union Center

Well Total Depth 4720 153.49 feet

Wichita, Kansas

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Union Drilg Company Inc License Number 5103 Tag # 4

Address Wichita, Kansas 67202

Company to plug at: Hour: 11:00 AM Day: 9th Month: Sept. Year: 1984

Plugging proposal received from Lyle Pason

(company name) Union Drilg Inc (phone) 316-262-2636

were: 8 5/8" - 365' SP CUL #1/180 SK Common Gel - Ca-cl. - (By Sun. Cnt) 2 1/2% 3%

Order 220 SK 50/50 Pozmix Gel - Ca-cl. - 1 SK 2 1/2% Cele - And 8 5/8" plug. 6% 3%

Spot with Drill Stem, Turn Hole Over - Heavy Mud Between All Plugs

No Circulation Problems, ELV. 2578 Ant. 2174, Perforable 4625

Plugging Proposal Received by M. J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 9th Month: Sept Year: 1984

ACTUAL PLUGGING REPORT

Ordered 220 SK 50/50 Pozmix Gel - Ca-cl - 1 SK 2 1/2% Cele - And 8 5/8" Plug 6% 3% SK Flo

Spotted with Drill Stem - Turned Hole Over, Heavy Mud Between All Plugs

1st Plug @ 4600' #1/25 SK cnt, 2nd Plug @ 2190' #1/25 SK cnt.

3rd Plug @ 1320' #1/100 SK cnt #1 SK Flo, 4th Plug @ 370' #1/50 SK cnt.

5th Plug ^{Solid Bridge} Halls - Plug @ 40' to 0' #1/10 SK cnt, 10 SK In Rat Hls (Cir)

Remarks: Cemented By Sun. Cnt

(If additional description necessary, use BACK of this form.)

INVOICED

DATE 9-21-84

INV. NO. 3829

SEP 17 1984
09-17-84
CONSERVATION DIVISION
Wichita, Kansas

Signed M. J. Schmidt (TECHNICIAN)