

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21417-00-00
Spot: E2NWSWNW Sec/Twnshp/Rge: 29-9S-21W
3630 feet from S Section Line, 4690 feet from E Section Line
Lease Name: KARST Well #: 1
County: GRAHAM Total Vertical Depth: 3872 feet

Operator License No.: 33937
Op Name: NEAL LAFON REALTY INC. DBA MERI
Address: 1475 WARD DR
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	213	0	w/unknown sxs cmt
PROD	4.5	3867	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/14/2009 11:00 AM
Plug Co. License No.: 32169 Plug Co. Name: DOPITA, DON DBA MAVERICK OIL CO.
Proposal Rcvd. from: BRETT HILDEBRAND Company: MERIDIAN ENERGY, INC. Phone: (785) 871-7311

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 700# hulls.
Perforated at 1100' - 200'.

125.84

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2009 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3780' - pumped 200 sxs 60/40 pozmix - 4% gel with 350# hulls.
Pulled tubing to 1850' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 800' - pumped 56 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 16 sxs 60/40 pozmix - 4% gel.
8 5/8" - 4 sxs 60/40 pozmix - 4% gel.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3867	3872		

INVOICED
DATE 6-16-09
INV. NO. 2009061612

RECEIVED
MAY 22 2009
KCC WICHITA

Remarks: ORIGINALLY KNOWN AS KARST #2. S.O.S. CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

Pat

MAY 19 2009

