

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21219-00-01
Spot: N2N2N2 Sec/Twnshp/Rge: 18-11S-18W
4950 feet from S Section Line, 2730 feet from E Section Line
Lease Name: FRISBIE A Well #: 2
County: ELLIS Total Vertical Depth: 3530 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	258	0	175 SX CXMT
PROD	5.5	3529	0	200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2009 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perf Tech perfed at 700'.
Well was flowing - had well shut off with drill mud - pumped down wellbore on 05/08/2009. Mud washed out and well was again flowing.

114.73

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2009 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing - stacked out at 1200'.
Swift Cementing rigged to tubing - pumped 250 sxs 60/40 pozmix - 4% gel with 500# hulls to circulate cement to pit.
Tubing was stuck in the hole. Turned off and left 20 joints in the hole.
Rigged to 5 1/2" casing with a swedge - pumped 100 sxs cement with 100# hulls.
No pressure. Left set 40 minutes.
Rigged to 8 5/8" - pumped 5 sxs cement.
Max. P.S.I. 250#. S.I.P. 250#.
Tied back onto 5 1/2" casing - pumped 45 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3181	3392		
3145	3149		
3070	3074		

RECEIVED
MAY 22 2009
KCC WICHITA

INVOICED
DATE 6-16-09

Remarks: SWIFT CEMENTING COMPANY-TICKET #15941.

INV. NO. 2009061618

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

MAY 11 2009

ROBERT R. PRICE OPERATING, INC. 'OWWO' 18-11-18W
 P.O. BOX 45442 #2 FRISBIE "A" "TWIN" 80'W.
 TULSA, OK 74145 C N/2 N/2 N/2
 CONTR RANGER DRLG. CO. CTY ELLIS

GEOL _____ FIELD COCHRAN WEST EXT (1/8 SE)

E 1911 KB CM 6/2/82 CARD ISSUED 9/2/82 IP P 13 80 & 127 BWPD
 1906 GL SHAW & LKC 3070-3392
 API 15-051-21,219-A OA

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1238	+ 673
TOP		2901	= 990
HEEB		3125	-1214
TOR		3143	-1232
LANS		3165	-1254
BKC		3393	-1482
CONG		3432	-1521
ARB		3515	-1604
TD		3469	-1558
RTD		3530	-1619

OLD INFO: OPERATOR WAS ROBERT R. PRICE, #1 FRISBIE, CONTR ALLEN DRLG, GEOL: ROBERT PRICE, SPD 10/4/76, SET 8 5/8" 258' 175SX, COMPLETED AS D&A/ARB 10/10/76

DST (1) 3160-3220, TIMES NA, REC 90' WM, SIP 1084-1064#, IP NA
 NEW INFO: RE-ENTERED ON 6/2/82, WSH DWN TO OTD, DDTD 3530, MICT - CO, PF (SHAW & LKC) 3070-3392 OA W/ 1 SPF, (SELECTIVE INTV'S NA), AC 15.500G, TSTD, POP, P 13 80 & 127 BWPD, (GR 29 6'), 8/6/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(NOTE: ORIG FR AS 100'W, C NW NW NE,
 #1 'B' FRISBIE)