

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00687-00-00

Spot: NENESW

Sec/Twnshp/Rge: 32-8S-24W

2341 feet from S Section Line,

2967 feet from E Section Line

Lease Name: HOLLEY

Well #: 10-1

County: GRAHAM

Total Vertical Depth: 3970 feet

Operator License No.: 30420

Op Name: INNONE, VINCENT DBA V.J.I. NATURA

Address: 3038 48TH ST

ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	206	0	140 SX
PROD	5.5	3986	0	100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/13/2009 12:00 PM

Plug Co. License No.: 33612

Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE

Proposal Rcvd. from: JASON DINGES

Company: V.J.I. NATURAL RESOURCES

Phone: (785) 623-8060

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 8 sxs gel spacer - 300# hulls.  
Perforated at 2125' - 1250' - 220'.  
Packer stuck in the hole at 3443'.

129.03

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/13/2009 4:15 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3300' - pumped 8 sxs gel spacer - followed with 75 sxs 60/40 pozmix - 4% gel and 200# hulls.  
Pulled tubing to 2100' - pumped 100 sxs 60/40 pozmix - 4% gel with 100# hulls.  
Pulled tubing to 1000' - pumped 80 sxs 60/40 pozmix - 4% gel to circulate cement to surface.  
Pulled all tubing. Topped off 5 1/2" casing with 30 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3906	3911		LANSING-KANSAS

INVOICED

DATE 6-16-09

INV. NO. 2009061619

RECEIVED

MAY 22 2009

KCC WICHITA

Remarks: ORIGINALLY KNOWN AS KEITH #1. ALLIED CEMENTING COMPANY-TICKET #43543.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

PKT

K &amp; E DRILLING

#1 KEITH

32-8-24W  
NE NE SW

Contr. K &amp; E DRLG GRAHAM County

E 2118 RB Comm. 4-27-55 Comp. 6-17-55 IP 306 BOPD  
PHY POT

Tops	Depth	Datum
ANH	2105	313
KC	3752	-1334
ID	3970	-1552

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Casing  
8" 206  
5" 3986  
DST 3867-91/1 HR, 25' MUD,  
SPKS OIL, BHP 750#  
DST 3898-3916/1 HR, 300'  
OIL, 1650' GAS, BHP 1200#  
DST 3917-70, 470' MUD;  
PERF 3906-11: 3 BOPH: ACID  
3000: S WB 16 BOPH
