

6 010304

API NUMBER 15-063-20888-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 20, T 11 S, R 26 W10

990 feet from S section line

4290 feet from E section line

Lease Name Reinecker Well, B-1

County Gove 149.18

Well Total Depth 4590 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 310 ✓

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Operator: F.M. Oil Co.

Name & Address 422 Union Center

Wichita Ks.

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Union Drlg. License Number 5103

Address Wichita Ks.

Company to plug at: Hour: 10 PM Day: 15 Month: 3 Year: 19 85

Plugging proposal received from Lyle Casen

(company name) Union Drlg. (phone) _____

were: Order 185 sx cem. 50/50 poz mix 6% Gel. 3% c.c.

Heavy mud between all plugs.

Pump cem. down drill pipe.

Elev. 2669 Anhydrite 2246-96 Arbuckle No.

Dakota - 1600 Plugging Proposal Received by Nate F. Balthezor

1069-1370 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part (None)

Operations Completed: Hour: 1:30 AM Day: 16 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT circ. @ 2270 for 20 mi.

25 SX @ 2270

100 SX @ 1370 w/ 1 SX Flow Seal

40 SX @ 330

10 SX @ 40 on Solid Bridge

10 SX in Ret Hole

MAR 25 1985

03-25-1985

Remarks: Cem. Co. Surv.

(If additional description is necessary, use BACK of this form.)

I (did 3-20-85 / did not) observe this plugging.

7429

Signed Nate F. Balthezor (TECHNICIAN)

3-22-85
3