

6 030403

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-063-20,889-00-00
NENUNNESEC. 36, T 11 S, R 22²⁰ (W)E

4950 feet from #(S) section line

1650 feet from #(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Thal Well # D-1

Operator: F & M Oil Co. Inc.

County Gove 147.91

Name & Address 422 Union Center

Well Total Depth 4551 feet

Wichita Kansas

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 340 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Union Drilg Co. Inc. License Number 5103

Address Wichita, Kansas

Company to plug at: Hour: AM Day: 25 Month: 3 Year: 19 85

Plugging proposal received from Syle

(company name) Union Drilg. Co. (phone) _____

were: 8 5/8" set @ 340' w/ 200' of 190' x 50' 50' x 6' log 3" pipe 8 5/8" w.p.

Circulate hole with no less than 36 Uis. mud and no loss of fluid. add 15' flo seal to 100' plug.

Sun Cement. Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30AM Day: 25 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT 4 1/2" Drill Pipe spotted at 2200' displace 25' x

Cement laydown D.P. to 1200' displace 100' x Cement 15' flo Seal

laydown D.P. to 360' displace 40' x Cement. laydown D.P.

Push wiper plug to 40 1/2' x hulls and Cement to base of cellar.

Displace 15' x Cement in Rathole from bottom to plow depth.

Plugging completed.

Remarks: Clear 2609 only 2177-2220 04-05-1985
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

4-9-85
7527

CONSERVATION DIVISION
Wichita, Kansas
Signed Carl Goodnow 4-7-85
(TECHNICIAN)