

KANSAS

4 STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

10-20-1971
RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1971
CONSERVATION DIVISION
Wichita, Kansas

15-063-20089-00-00

Operator's Full Name Pacific Oil and Gas Company,

Complete Address Colcord Building, Oklahoma City, Oklahoma.

Lease Name Inloe Well No. 1

Location CHE-NE Sec. 10 Twp. 11 Rge. (E) (W) 26

County Gove Total Depth 4098'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company.

Address Box #1164, Great Bend, Kansas. License No.

Operation Completed: Hour 1:00 AM Day 18 Month 10 Year 1971

The above well was plugged as follows:

305'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 825'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 10-20-71

INV. NO. 4501-42