

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-063-20092-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1969
CONSERVATION DIVISION
Wichita, Kansas

10-06-1969

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name Flora Well No. C-1

Location APP C NE NE
660' ENL & 560' FEL Sec. 3 Twp. 11 Rge. (E) (W) 26

County Gove Total Depth 4630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Bldg., Wichita, Kans. License No.

Operation Completed: Hour 2:30 PM Day 1 Month 10 Year 1969

The above well was plugged as follows:

357'-8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1118'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement thru
DP from 1350' to 1025'. Pulled DP to 390' and displaced 20 Sx. cement thru DP from
390' to 330'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

NOTICE
DATE 10/6/69
INV. NO. 596-41