

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-063-20095-00-00

Operator's Full Name Herndon Drilling Company,

Complete Address Box #489, Tulsa, Oklahoma.

Lease Name Bedard Well No. 1

Location SE-SE-NW Sec. 28 Twp. 11 Rge. (E) (W) 26

County Gove Total Depth 2890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address Box #352, Russell, Kansas. License No.

Operation Completed: Hour 1:30 PM Day h Month 12 Year 1971

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
thru DP from 1275' to 950'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set plug @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. S. Nichols*
Well Plugging Supervisor

12/8/71
4788-W