

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-109-20,326-00-00

SE SE SE Sec. 32, T 11 S, R 32 (W)

330 feet from N/S section line

330 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5053

Lease Name Holmberg Well # 1

Operator: Petro-Dynamics
Name & 555 N. Woodlawn
Address Building 1 Suite 207
Wichita, Ks. 67208

County Logan

Well Total Depth 4720 feet *15340*

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 287 205 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Kandrill Co., Inc. License Number 5889

Address Same as above

Company to plug at: Hour: PM Day: 29 Month: June Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Larry Hicks

(company name) Kandrill Co., Inc. (phone)

were: Order 205 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8⁵/₈" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 6:30 PM Day: 29 Month: June Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 2610 w/25 sks

2nd plug @ 1650 w/100 sks w/1 sk flo-cel

3rd plug @ 290 w/50 sks

4th plug @ 40 w/8⁵/₈" plug 1/2 sk hulls 10 sks cmt.

10 sks in Rat Hole and 10 sks in Mouse Hole

Cemented by Sun Cementing Company.

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did-/ did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 7-16-84

07-09-1984
1111 09 1984

WEL NO. 2510 CONSERVATION DIVISION
6-29 Wichita, Kansas

Signed Gilbert P. Laska
(TECHNICIAN)

July 2