

6040143

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22, 378-00-00
SW SW SW, SEC. 35, T 12 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6343

_____ feet from N/S section line
_____ feet from W/E section line

Operator: Yost Oil Operation
Name & Address P.O. BOX 811

Lease Name Starky Well # A #1
County Russell

Russell, Ks. 67665

Well Total Depth 3115 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 643' w/300

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Emphasis License Number 622

Address Russell, Ks. 67665

Company to plug at: Hour: Late PM Day: 13 Month: June Year: 19 84

Plugging proposal received from Ben Griffin

(company name) Emphasis (phone) _____

were: Order 160 sks. 50/50 pozmix 6% gel 3% cal. cl. and 8 5/8" plug. Spot with drill

pipe with no less than 36 vis. mud between all plugs, with good circulation

and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 7:15 PM Day: 13 Month: June Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 650 w/100 sks

2nd plug @ 200 w/40 sks

3rd plug @ 40 w/10 sks (solid bridge)

10 sks in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION

FILL IN 02 1984
07-02-1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(if additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

DATE 7-11-84

INV. NO. 2395

Signed Dennis L. Hamel
(TECHNICIAN)