

4-020063

9-24

AP 15-167-19003-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 03-09-62  
C N2 S2 /4 SEC. 02, 12 S, 15 W  
1980 feet from S section line  
2640 feet from E section line

Operator license# <sup>100</sup> ~~0000~~  
Operator: State of Kansas Fee Fund  
Address: 2301 E. 13th Street  
Hays, Kansas 67601  
Control #990013-002

Lease: Shaffer Well # 3  
County: Russell  
Well total depth 3400 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Kansas Corporation Commission License# -

Address: 2301 E. 13th Street - Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: September Year: 1998

Plugging proposal received from: Herb Deines

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Ordered 350 sxs 60/40 pozmix - 10% gel - 1200# hulls.  
Well completed as disposal well but was never permitted. Evidence showed water was  
being disposed of from surface. Casing above surface was eaten up.

8661-10-01

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 24, Month: September, Year: 1998

Actual plugging report: 8 5/8" set at 265'. 5 1/2" set at 3330'.  
Perforated 5 1/2" at: 1425' bottom of salt section. 860' bottom of anhydrite and  
400' bottom of dakota. Ran tubing to 1569' and spotted 75 sxs cement with 300# hulls.  
Pulled tubing to 785' and pumped 80 sxs cement with 200# hulls. Pulled tubing out of hole  
and tied onto 5 1/2" and pumped 50 sxs cement. Max. P.S.I. 600#. S.I.P. 300#. Tied onto  
annulus and pumped 5 sxs cement. Max. P.S.I. 400#. S.I.P. 200#.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD BAD X  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: 1764 GL

I did [ X ] / did not [ ] observe the plugging.

*Jay F. Feigler*  
(agent)