

15-167-21999-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NE, Sec. 2, T 12 S, R 15 (W)E
330 feet from (N)S section line
990 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6111

Lease Name Eulert Well # 1

Operator: N-B Company, Inc.
Name & Address P.O. Box 506, Russell, Ks. 67665

County Russell

Well Total Depth 3309 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 250'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelson Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Ks. 67524

Company to plug at: Hour: 9:30 AM Day: 4 Month: 1 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Mike Kelson

(company name) Kelson Casing Pulling (phone) 316-938-2457

were: Order 165 lbs. 50 posmix - 4% del., -3% lat. cl., 5 lbs. hulls, 15 lbs. del. & 8 5/8" plug.

Signed Walter J. Lohel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 AM Day: 4 Month: 1 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 250' S.P. cas. w/ 150 lbs cement, 5 1/2" set at 3303' w/ 75 lbs. 6' of open hole. Plugged bottom w/ 5 lbs cement, sand & 5 lbs. cement. Shot pipe 2 times & recovered 2803'. Pumped in 8 5/8" S.P., 4 lbs. hulls, 12 lbs. del., 65 lbs. cement, 3 lbs. del., 1 lb. hulls, released plug & followed w/ 100 lbs. cement.

Maximum pressure 600 pounds.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
01-10-1983
JAN 10 1983

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

REC'D
1-12-83
2103-W

Signed Walter J. Lohel
(TECHNICIAN)