

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-167-00252-00-00

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 35 TWP. 12 RGE. 14 <sup>W</sup>

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. B-1 Lease Steinert

Operator Prairie Oil Well Drillers Address c/o Dude Zimmerman  
Russell, Kans

Field \_\_\_\_\_ County Russell

Total Depth 3035 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" set at 626' - 5 1/2" at 2847 with 500 sax cement,  
Bottom cemented of, top perforations at 2452', Lane - wells  
plugs at 2471'.

Pulled 1950' of 5 1/2", pumped hole full heavy mud with  
Halliburton, set plug at 650' with 10 sax cement on plug,  
Pulled 360' of 8 5/8", filled hole with heavy mud to 110',  
set rock bridge and 15 sax cement, filled hole to 55', with  
heavy mud, set wood plug, rock bridge and 20 sax cement.

**PLUGGING**  
FILE SEC. 35 TWP. 12 R. 14 <sup>W</sup>  
BOOK PAGE 145 LINE 28

Edwin J. Petty 03-30-1950  
District Conservation Agent  
Date 3-28-50