

DISTRICT CONSERVATION AGENT'S REPORT

15-167-00381-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 55 TWP. 12 RGE. 14

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Steinard

Operator Prairie Oil Well Drillers Address (Dude Zimmerman - Russell, Kans)

Field _____ County Russell

Total Depth 3075 Feet.

(Describe briefly the manner in which the well was plugged)

12-81', 10"- 500', 8 5/8"- 500', 7"- 2500', 5 1/2" - 2880,

Pulled 5 1/2" and 7", mudded hole to 500', set wood plug, pulled

8" and 10", mudded hole to 155', set wood plug and 50 sack cement,

pulled 12", mudded hole to 20', set rock bridge and 25 sack cement.

District Conservation Agent

Date 11-18-49 11-22-1949

PLUGGING
FILE SEC. 35 T. 12 R. 14
BOOK PAGE 125 LINE 40