

DISTRICT CONSERVATION AGENT'S REPORT

R

15-167-00136-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SE-SW

SEC. 1 TWP. 12 RGE. 15W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mellard

Operator Bell Oil & Gas Company. Address Box 2007. Tulsa, Okla.

Field _____ County Russell

Total Depth 3245' Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contractor.- Transit Corporation.

Plugging Contractor's License No.-

Address.- 1516 Liberty Bk. Bldg. Oklahoma City, Okla.

Surface pipe - 8 5/8" @ 183' c.w.c. 125 sx.

Filled hole with heavy mud to top, H.O.W.C.O. plug and squeezed

with 80 sx. cem. to base of cellar.

Halliburton Oil Well Cementing Company did the job.

PLUGGING
FILE SEC 1 T. 12 R. 15W
BOOK PAGE 85 LINE 23

RECEIVED
STATE CORPORATION COMMISSION

JUN 21
07-31-1956

Victor Suber
District Conservation Agent

Date 7-23-56

On July 24th. went out to location to check as to how far cement had settled down, it had settled 38' and we noticed that we had a Dakoto flow. So shut valve back up and contacted Lawrence Walters with Transit Corp. and advised him of the situation.

So I suggested to Mr. Walters that we get a pump truck and see if we could pump into the well. So on July 26th. we got Halliburton pump truck and found that we could pump into the well. So we ordered out some cem. mixed with 2% Calcium Chloride and pumped in 34 sx. cem. with a pressure up to 1500 pounds.