

DISTRICT CONSERVATION AGENT'S REPORT

15-167-60264-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 28-13

LOCATION SW-SW-SW

SEC. 2 TWP. 12 RGE. 15W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Shaffer "B"

Operator Chester Loving. Address 907 East Second St.
Russell, Kansas.

Field _____ County Russell

Total Depth 3142' Feet.

Plugging Contractor Forbes Casing Pulling Company.

Plugging Contractor's License No. 119

Address Great Bend, Kansas.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 8 5/8" @ 716' c.w.c. 400 sx.. 5 1/2" @ 3115' cem. with
75 sx. Lane Well's Plug @ 2850' and 1 sx. cal- Seal. Perforated from
2820' to 2828'. Chat back to 2800' and 5 sx. cem. with dump bailer. Shot
5 1/2" off @ 2362' and pulled up to approx 1180', got Halliburton pump
truck, and pumped in 50 sx. of jell mud, circulated. Pulled pipe out.
Bailed fluid down to 300' from top, set plug, rock bridge and 20 sx. cem.
Mud to 35' from top, set plug, rock bridge and 10 sx. cem. to base of cellar.

Milton Galusha
District Conservation Agent

Date 8-4-57

RECEIVED
STATE CORPORATION COMMISSION
08-07-1957
AUG 7 1957

PLUGGING
FILE SEC 2 T 12 R 15W
BOOK PAGE 28 LINE 13

CONSERVATION DIVISION
5