

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-167-00004-00-00

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 33-24

LOCATION S<sup>3</sup>NE-NE-SW

SEC. 2 TWP. 12 RGE. 15W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \*\*\* Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Shaffer

Operator Morgenstern & Specter Address Box 661. Russell, Kansas.

Field \_\_\_\_\_ County Russell

Total Depth 3250' Feet.

Plugging Contractor Forbes Casing Pulling Company.

Plugging Contractor's License No. 49

Address Great Bend, Kansas. Box 221.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 8 5/8" @ 185' c.w.c. 125 sx.. 5 1/2" set @ 3239' cem.  
with 100 sx. Chat back to 3225' and 5 sx. cem. with dump bailer.  
Picked up on pipe and it pulled apart @ 464' then pulled same. Did not  
bother to fish for remainder of pipe. Got Globe Oil Well Cem. Co. to  
pump in 25 sx. of jell mud, plug and 50 sx. cem.. Next day bailed water  
off and found top of cem. at approx 80' from base of cellar. Then mud  
to 35' from top, set plug, rock bridge and 10 sx. cem. to base of cellar.

Milton G. Gandy  
District Conservation Agent

Date 9-14-57

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 21 1957  
09-17-1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 2 T. 12 R. 15W  
BOOK PAGE 33 LINE 24