

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 093-00188-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: XTO Energy, Inc. KCC License #: 32864

Address: 210 Park Ave., Suite 2350 City: Oklahoma City

State: OK Zip Code: 73102 Contact Phone: (405) 319 - 3212

Lease: Widner Well #: 1-9 Sec. 9 Twp. 23 S. R. 38 East West

C SE Spot Location / QQQQ County: Keamy

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 332' Cemented with: 200 Sacks

Production Casing Size: 5 1/2" Set at: 2710' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2618'-32, 2668'-78', 2680'-84' & 2651'-52'(squeezed)

Elevation: 3363' (G.L. / K.B.) T.D.: 2723' P.B.T.D.: 2705' Anhydrite Depth: 2050'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Cement plug 2565'-2615' (over perfs), cement plug 2000'-

2100' (Anhydrite @ 2050'), cut off casing at freepoint & pump a 100' cement plug (50' above and 50' below casing stub),

cement plug 230'-380' (surface casing & BTW), cement plug 4'-34' (at surface), weld on identification plate

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

KANSAS CORPORATION COMMISSION
JUL 10 2009
RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Littell & Mark Gosch

Phone: (620) 272 - 1780 or 272-1996

Address: 805 S. Hwy 25 City / State: Lakin, KS

Plugging Contractor: Not selected at this time Orr Enterprize KCC License #: 33338

Address: _____ Phone: () - _____

Proposed Date and Hour of Plugging (if known?): Not known at this time

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/8/09 Authorized Operator / Agent: Karen Byers (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

XTO ENERGY INC.
210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102-5683

July 10, 2009

Re: WIDNER #1
API 15-093-00188-00-00
9-23S-38W, 1320 FSL 1320 FEL
KEARNY COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after January 6, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,



Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888