

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6445
Name: Miller Brothers Oil Co Inc
Address 1: 701 W4th
Address 2: _____
City: Lebo State: Ks Zip: 66856 + _____
Contact Person: Daniel Horst
Phone: (620-) 344-1518

API No. 15 - 073-21,873 -0000
If pre 1967, supply original completion date: _____
Spot Description: 660 Wel, 660 NSL SE 1/4
~~use~~ Sec. 20 Twp. 23 S. R. 13 East West
660 Feet from _____, rth / South Line of Section
660 Feet from East / _____ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Greenwood
Lease Name: Lingenfelter Well #: 3

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 42 ft Cemented with: 25 Sacks
Production Casing Size: 4 1/2 Set at: 1759 Cemented with: 75 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Perforated with 10 holes 1706 to 1711 Mississippi Lime

Elevation: _____ (G.L. / K.B.) T.D.: _____ PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

See attached page Plug set at and above perforations gravel and 3 sacks cement for summary see attached field ticket and treatment report cement

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

KANSAS CORPORATION COMMISSION

JUN 19 2009

RECEIVED

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Daniel Horst

Address: 1707 Yucca Lane City: Emporia State: Ks Zip: 66801 + _____

Phone: (620) 344-1518

Plugging Contractor License #: 7719 Name: Cheever Well Service

Address 1: 1016 Sw Blvd Address 2: _____

City: Madison State: Ks Zip: 66852 + _____

Phone: (620) 437-2296

Proposed Date of Plugging (if known): upk 2/2/09 8am

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-2-09 Authorized Operator / Agent: Daniel Horst
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Well plugged - KCC - ACT

Dist 3
PK



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 20807
LOCATION Eureka
FOREMAN Troy Strickler

PO Box 884, Chanute, KS 66720
820-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT
CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
2-2-09	5197	Lingenfelter # 3				GW
CUSTOMER Miller Brothers Oil			TRUCK #			
MAILING ADDRESS 701 West 4th			DRIVER			
CITY Lebo			TRUCK #			
STATE KS		ZIP CODE 66856	DRIVER			
			520 Clif			
			543 Dave			

JOB TYPE P.T.A. HOLE SIZE 7 7/8" HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2"
 CASING DEPTH _____ DRILL PIPE _____ TUBING 2 3/4" OTHER _____
 SLURRY WEIGHT 14# SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT IN CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: Rig up to 2 3/4" Tubing set @ 1466'. Spot 15sk Plug. Pull tubing to 913' spot 25sk Plug. Pull tubing to 160'. Pump 100sk Cement to surface. Pull tubing. Top hole off. Pump Gel spacers between Plugs.
Job Complete.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	590.00	590.00
5406	30	MILEAGE	3.45	103.50
1131	140sk	60/40 Poz-Mix Cement	10.70	1498.00
1118A	480#	Gel 4%	.16#	76.80
1118A	300#	Gel spacers	.16#	48.00
5407		Ton-mileage	m/c	296.00
KANSAS CORPORATION COMMISSION				
JUN 19 2009				
RECEIVED				
<u>Thank u!</u>				
			Sub Total	2612.30
			SALES TAX	102.25
			ESTIMATED TOTAL	2714.55

Rev'n 3737

208646

AUTHORIZATION _____ TITLE _____ DATE _____



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 228646

Invoice Date: 02/04/2009 Terms: 0/30,n/30

Page 1

MILLER BROTHERS OIL
701 WEST 4TH
LEBO KS 66856
(620)256-0108

LINGENFELTE #3
20807
02-02-09

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX-	140.00	10.7000	1498.00
1118A	S-5 GEL/ BENTONITE (50#)	480.00	.1600	76.80
1118A	S-5 GEL/ BENTONITE (50#)	300.00	.1600	48.00
	Description	Hours	Unit Price	Total
520	P & A OLD WELL	1.00	590.00	590.00
520	EQUIPMENT MILEAGE (ONE WAY)	30.00	3.45	103.50
543	MIN. BULK DELIVERY	1.00	296.00	296.00

KANSAS CORPORATION COMMISSION

JUN 19 2009

RECEIVED

citizens Pd 2/9/09
9823
2714.53

Parts:	1622.80	Freight:	.00	Tax:	102.23	AR	2714.53
Labor:	.00	Misc:	.00	Total:	2714.53		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____

BARTLESVILLE, OK
918/338-0808

ELDORADO, KS
316/322-7022

EUREKA, KS
620/583-7664

GILLETTE, WY
307/686-4914

MCALISTER, OK
918/426-7667

OTTAWA, KS
785/242-4044

THAYER, KS
620/839-5269

WORLAND, WY
307/347-4577

Well Plugging Report
Lingenfelter #3

A casing leak was detected with salt water coming from the Douglas formation contaminating the producing formation.

A gravel plug was set over the perforations with 3 sacks of cement on top of the gravel with the intention of when the well squeezing was completed, drilling the plug out and returning the well to production.

In the process a 4 ½ packer was run to find the hole in the pipe and during the setting process the casing parted and collapsed.

900 feet of casing was recovered from the well

We were able to run 2 ½ Eue tubing to a depth of 1466 and pump in 15 sacks of cement the tubing was pulled to a depth of 900 feet and 25 sacks of cement was spotted at that depth. The tubing was pulled to a depth 160 feet with 100 sacks of cement spotted to surface and the top of the hole was topped off . Gel spacers was spotted between the plugs .

KANSAS CORPORATION COMMISSION

JUN 19 2009

RECEIVED