

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-24553-00-00  
Spot: NENWNESW Sec/Twnshp/Rge: 21-32S-10E  
2470 feet from S Section Line, 3340 feet from E Section Line  
Lease Name: MCALISTER Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 2268 feet

Operator License No.: 32912  
Op Name: CARROLL ENERGY, LLC  
Address: 200 ARCO PL STE 230 PO BOX 149  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	79		55 sx
PROD	5.5	2306		100 SX

Well Type: EOR UIC Docket No: E23693.1 Date/Time to Plug: 05/22/2009 9:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SET BRIDGE PLUG AT 2010', 50' PLUG ON TOP OF BRIDGE PLUG, 50' PLUG AT 900' AND 500' TO SURFACE.  
73.71

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/22/2009 11:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

SET BRIDGE PLUG AT 2010'. RAN 2 7/8" PIPE TO 2000' GELLED HOLE WITH 15 SACKS OF GEL AND SPOTTED 20 SACK PLUG. PULLED 2 7/8" UP TO 900' AND SPOTTED 15 SACK PLUG. PULLED 2 7/8" UP TO 500' AND CIRCULATED CEMENT TO SURFACE. PULLED PIPE AND TOPPED WELL OFF. A TOTAL OF 122 SACKS OF CEMENT WERE USED TO PLUG THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAY 22 2009 DAS

CHANUTE, KS


INVOICED  
MAY 27-13-09  
INV. NO. 2010060006

RECEIVED  
MAY 29 2009  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed   
(TECHNICIAN)