

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20140-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 6-15S-42W
3500 feet from S Section Line, 4820 feet from E Section Line
Lease Name: ARAPAHOE UNIT Well #: 113
County: WALLACE Total Vertical Depth: 5300 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	686	0	275 SX
PROD	4.5	5296	0	150 SX

172.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2009 9:00 AM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: HERSCHEL KENNEDY Company: CITATION OIL & GAS CORPORATI Phone: (719) 340-1150

Proposed Plugging Method: Ordered 150 sxs common cement - 3% c.c. - 20 sxs gel.
Plug through tubing.
05/12/2009 - Ordered 25 sxs common cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2009 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

05/05/2009
8 5/8" surface pipe set at 686' w/275 sxs cement.
4 1/2" production casing set at 5296' w/150 sxs cement.
Cement sleeve at 1955' - cemented with 400 sxs.
CIBP set at 5124' - cemented with 2 sxs.
Production casing filled with gelled water from 5124' to 600'.
Production casing perforated at 2860'.
Ran tubing to 2860' - pumped 30 sxs cement.
Pulled tubing to 2000' - pumped 35 sxs cement.
Pulled tubing to 735' - pumped 30 sxs cement.
Pulled tubing to 120'. Circulated cement to surface with 15 sxs.
Pulled tubing to surface.
Topped 4 1/2" production casing with 10 sxs cement. Cement falling.
Connected to 8 5/8" surface casing - pumped 30 sxs cement.
Used all 150 sxs cement.
05/12/2009
Topped 4 1/2" production casing with 10 sxs cement. Plug complete.

Perfs:

Top	Bot	Thru	Comments
5154	5164		MORROW

INVOICED
DATE 7-13-09
INV. NO. ~~200~~ 2010060007
RECEIVED
MAY 26 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #43914.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

MAY 21 2009

PPT

TXO PRODUCTION CORPORATION
WICHITA, KS 67202

6-15 -42W
3500'FSL & 4820'FEL, SEC

#2 HIBBERT "B"

site: 5-3/4 S & 3-3/4 W OF WESKAN, KS
contr: MURFIN DRILLING COMPANY

cty: WALLACE
field: ARAPAHOEKAN

API 15-199-20140

geol:
fr date 02/17/88 spd date 02/19/88 drtg comp 03/03/88 card issued 11/09/88 last revised 11/09/88

ELV: 3930 KB LOG
tops.....depth/datum
B/SC.....2874 +1058
RED CV SD.....2940 +990
NEVA.....3450 +480
FOR.....3620 +310
WAB.....3750 +180
TOP.....3957 -27
HEEB.....4182 -252
LANS.....4276 -346
MARM.....4645 -715
FT SC.....4723 -793
CHER.....4776 -846
ATOKA.....4902 -972
MRW.....5060 -1130

IP status:
OIL, P 169 BOPD, NW & 9 MCFGPD, MRW 5154-5164 ,
MRW SD LWR.....5152 -1222
MRW LM LWR.....5184 -1254
MISS.....5198 -1268
PBD.....5283 -1353
RTD.....5300 -1370
CSG: 8-5/8" 686 / 275 SX, 4-1/2" 5300 / 150 SX
NO CORES OR DSTS
MICT - CO, PF (MRW) 5154-5164, W / 4 SPF, GSO & G,
NAT, SET 2-3/8" TBG AT 5220, POP, P 169 BOPD, NW &
9 MCFGPD (GR 40), 3/12/88

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS