

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-00525-00-01  
Spot: SWNWNE Sec/Twnshp/Rge: 11-1S-27W  
4313 feet from S Section Line, 2442 feet from E Section Line  
Lease Name: WARNER UNIT Well #: 105W  
County: DECATUR Total Vertical Depth: 3435 feet

Operator License No.: 31660  
Op Name: ROBUCK, DON E. DBA ENERGY SEARC  
Address: PO BOX 31697  
AURORA, CO 80041

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	320	0	w/250 sxs cmt
PROD	5.5	3434	0	w/200 sxs cmt

111,64

Well Type: EOR UIC Docket No: E12401.1 Date/Time to Plug: 05/20/2009 11:00 AM  
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY  
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK, DON E. DBA ENERGY SE Phone: (303) 345-7200

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 10 sxs gel spacer - 700# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/20/2009 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 320' w/250 sxs cement.  
5 1/2" production casing set at 3434' w/200 sxs cement.  
TD 3435'. PBTD 3350'. Perforated production casing at 1945' and 1300'.  
Ran tubing to 3434' - pumped 10 sxs gel with 50# hulls - followed w/50 sxs cement w/200# hulls.  
Pulled tubing to 1950' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1300' - pumped 105 sxs cement with 250# hulls.  
Cement circulated to surface.  
Pulled tubing to surface. Topped production casing with 20 sxs cement.  
Connected to 8 5/8" surface casing - pumped 50 sxs cement.  
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3280	3289		
3239	3242		
3229	3234		
3198	3206		

RECEIVED  
MAY 27 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37466.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM  
PET

Form CP-2/3

MAY 21 2009

CITIES SERVICE OIL CO

#5 SATER

11-1-27W  
SW NW NE

Contr. LOHMAN-JOHNSON

DECATUR

County

E 2533

Comm. 10-5-56

Comp. 11-16-56

IP

56 BOPD

Tops	Depth	Datum
HOW	2924	-391
SEV	3009	-476
TOP	3026	-493
HEEB	3151	-618
DOD	3174	-641
LANS	3192	-659
B/KC	3409	-876
PENN SND	3415	-882
TD	3435	-902

Casing  
 8" 320  
 5" 3434  
 DST 3195-3215/1 HR, 36' M, 2' O, BHP 500/  
 DST 3230-50/1 HR, 6' OCM, 1' O, BHP 0/  
 DST 3279-3300/1 HR, 18' M, 10' H OCM, BHP  
 800/  
 DST 3308-27/1 HR, 5' M, BHP 0/  
 DST 3399-3420/1 HR, 6' M, BHP 400/  
 PERF 3198-3289: ACID 3000: 20 BO & 17  
 BW/24 HRS

WARNER POOL

+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS