

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22684-00-00  
Spot: S2NWNWNW Sec/Twnshp/Rge: 1-34S-39W  
400 feet from N Section Line, 330 feet from W Section Line  
Lease Name: BURROWS Well #: 1 #1  
County: STEVENS Total Vertical Depth: 7650 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1678		WITH 480 SX CMT

248.63

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2009 4:30 AM  
Plug Co. License No.: 34000 Plug Co. Name: KENAI MID-CONTINENT, INC.  
Proposal Rcvd. from: PRESTON HEISKELL Company: EOG RESOURCES Phone: (405) 246-3100

Proposed Plugging Method: 1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: NONE  
Date/Time Plugging Completed: 05/20/2009 6:30 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

RECEIVED  
MAY 13 2009  
AV No. 2010060011

RECEIVED  
MAY 20 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: DP

District: 01

RECEIVED  
MAY 20 2009

KCC DODGE CITY

Signed \_\_\_\_\_

(TECHNICIAN)