

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-01502-00-00<sup>01</sup>  
Spot: SWNENE Sec/Twnshp/Rge: 29-23S-14E  
4520 feet from S Section Line, 760 feet from E Section Line  
Lease Name: MACLASKEY JW Well #: 15  
County: WOODSON Total Vertical Depth: 1706 feet

Operator License No.: 8093  
Op Name: HAAS, GARY L. DBA GARY HAAS - OIL  
Address: 600 ARROWHEAD DR  
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		55, 45
T1	2.375	1589		
PKR		1589		
PROD	5.5	1680		

Well Type: EOR UIC Docket No: E12212.3 Date/Time to Plug: 05/18/2009 10:00 AM  
Plug Co. License No.: 6527 Plug Co. Name: TITUS WELL SERVICE  
Proposal Rcvd. from: GARY HAAS Company: TITUS WELL SERVICE Phone: (620) 364-5893

Proposed Plugging Method: THIS WELL CONSISTED OF 5 1/2" CASING TO 1698' THAT HAD BEEN CEMENTED IN FROM 159' TO SURFACE. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG, FROM BORE WALL TO BORE WALL, AT T.D., A 50' CEMENT PLUG AT 700' AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE  
Date/Time Plugging Completed: 05/18/2009 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE 5 1/2" CASING WAS PERFORATED 650', 700', AND 160' AND 200'. 15 SACKS OF CEMENT WERE SPOTTED AT T.D.. 15 SACKS OF CEMENT WERE SPOTTED AT 700'. THE WELL WAS CIRCUCLATED FULL OF CEMENT FROM 200' TO SURFACE.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAY 27 2009 CPT

CHANUTE, KS

NO. 010  
7-13-09  
2010060013

RECEIVED  
MAY 28 2009  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)