

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21594-00-02
Spot: S2SWSW Sec/Twnshp/Rge: 9-24S-15W
330 feet from S Section Line, 660 feet from W Section Line
Lease Name: O'CONNOR GU Well #: 3-1 RALPH
County: STAFFORD Total Vertical Depth: 4100 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3070		133.25
CIBP		3200		
CIBP		3750		
CIBP		3965		
SURF	8.625	333		WITH 210 SX CMT
PROD	5.5	4099	1900	WITH 400 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/08/2009 12:45 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. TAG TOC. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2009 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 25 SX CMT. TAG TOC @ 2900'. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG AT 360' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4049	4051		
3847	3851		
3811	3815		
3773	3777		
3732	3736		
3646	3648		
3085	3089		
3047	3053		

INVOICED
DATE 7-13-09
INV. NO. 2010060017
RECEIVED
MAY 26 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

KCC WICHITA

Plugged through: CSG

RECEIVED

District: 01

MAY 14 2009

Signed

Stephen J Pfeifer
(TECHNICIAN)

KCC DODGE CITY

RAWX