

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-01267-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 28-19S-2W  
2293 feet from S Section Line, 1042 feet from E Section Line  
Lease Name: JJ KOEHN Well #: 4  
County: MCPHERSON Total Vertical Depth: 3566 feet

Operator License No.: 5631  
Op Name: LOEWEN OPERATOR, INC.  
Address: 208 S MAIN PO BOX 335  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	<u>8 7/8</u>	160		<u>115.90</u>
PROD	5.5	3566		

Well Type: SWD UIC Docket No: D27579.0 Date/Time to Plug: 05/06/2009 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 654-8342

Proposed Plugging Method: PUMP 35 SX @ 2700'. PERFORATE AT 450' AND CIRCULATE TO SURFACE FROM 450'.

Plugging Proposal Received By: GREG EVES WitnessType: NONE  
Date/Time Plugging Completed: 05/07/2009 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

PERFORATED CASING AT 450' . RAN TUBING TO 2700' AND PUMPED 35 SX CEMENT WITH POLYFLAKE AND 3% CALCIUM CHLORIDE. TAGGED CEMENT AT 2244'. RAN TUBING TO 450' AND PMPED 240 SXS TO CIRCULATE TO SURFACE. RAN 1" DOWN BACKSIDE AND PUMPED 84 SXS TO CIRCULATE TO SURFACE. PUMPED 50 SX TO TOP OFF 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
3066	3102		
3016	3044		

INVOICED  
DATE 7-13-09  
NO 2010060019

RECEIVED  
MAY 27 2009  
KCC WICHITA

Remarks: CONSOLIDATED WELL SERVICE TICKET #20922. TOTAL 275 SX ON 5/6/2009. TICKET #20923 TOTAL 134 SXS ON 5/7/2009 GRAND TOTAL 414 SX CEMENT 60/40 POZ 4% GE

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)