

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-19245-00-00
Spot: NENWNW Sec/Twnshp/Rge: 13-31S-9E
5004 feet from S Section Line, 4342 feet from E Section Line
Lease Name: WISEMAN Well #: 1
County: ELK Total Vertical Depth: 2307 feet

Operator License No.: 31119

Op Name: WOLFE, ROBERT & DEBBIE S. DBA Lone wolf oil.

74.98

Address: BOX 241
MOLINE, KS 67353

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2008 12:00 AM

Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at 2280', 50' plug at 1000', perforate at 500' and circulate cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/27/2008 12:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Well was filled sand and lime chips from 2307' to 2280'. Put 5 sacks of cement at 2280' and 5 sacks at 1000' with bailer. Perforated pipe at 441' and circulated cement to top through casing. A total of 85 sacks of 60/40 pozmix cement with 4% gell was used to plug this well.

RECEIVED
KCC DISTRICT #3

MAY 26 2009 DAS

CHANUTE, KS

INVOICED
DATE 7-13-09
INV NO. 2010060020


RECEIVED
MAY 29 2009
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed



(TECHNICIAN)