

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-19246-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 13-31S-9E
4991 feet from S Section Line, 4686 feet from E Section Line
Lease Name: WISEMAN Well #: 2
County: ELK Total Vertical Depth: 2307 feet

Operator License No.: 31119

Op Name: WOLFE, ROBERT & DEBBIE S. DBA LO ne wolfoil

Address: BOX 241
MOLINE, KS 67353

74.98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2008 8:00 AM

Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' PLUG AT 2275', 50' PLUG AT 1500' AND PULL CASING FROM 500' AND CEMENT TOP 500'.

Plugging Proposal Received By: DUANE SIMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/27/2008 12:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Hole was filled with sand and lime chips from 2307' to 2275'. Ran 5 sacks of cement with bailer to 2275'. Put 5 sacks of cement at 1500' with bailer. Shot casing off at 528' and pulled. Ran 2" to 510' and circulated 60/40 pozmix cement with 4% gel to surface. Pulled 2" and topped well off. A total of 110 sacks of cement were used to plug this well.

RECEIVED
KCC DISTRICT #3

MAY 26 2009

DAS

WICHITA, KS

NOV 10 2009
7-13-09
ENV NO. 2010 060020

RECEIVED

MAY 29 2009

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Duane A. Sims

(TECHNICIAN)

PFT