

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21930-00-01
Spot: NENW Sec/Twnshp/Rge: 36-31S-13W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KIMBALL 2 Well #: C
County: BARBER Total Vertical Depth: 4215 feet

Operator License No.: 31406
Op Name: PRAIRIE RESOURCES, INC.
Address: 2530 NW WILLOW RD
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		WITH 2 SX CMT 136.99
CIBP		4100		
SURF	8.625	350		WITH 225 SX CMT
PROD	4.5	4214	2500	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2009 9:45 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 3850' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: NONE
Date/Time Plugging Completed: 05/21/2009 10:45 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

CIBP @ 3850' & 2 SX CMT. SPOT PLUGS THROUGH 2 3/8" TBG. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4161	4167		MISSISSIPPI
3890	3893		LANSING

NOVED
DATE: 7-13-09
INV NO: 2010060022
RECEIVED
MAY 26 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed _____

RECEIVED
MAY 21 2009

(TECHNICIAN)

KCC DODGE CITY