

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01504-00-01
Spot: NWNWSW Sec/Twnshp/Rge: 12-9S-17W
2210 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MCCLAY Well #: 4
County: ROOKS Total Vertical Depth: 3436 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	190		50 SX
T1	2.375	3052		111.67
DVT		872		
PKR	7	3328		
PROD	5.5	3433	0	200 SX

Well Type: EOR UIC Docket No: E10080.2 Date/Time to Plug: 05/22/2009 12:00 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: PROSPECT OIL & GAS CORP. Phone: (785) 324-1041

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Tubing parted - washed over several time - only recovered 1345' of tubing (swiss cheese).
Injection perfs: 3130' - 3384'.
Squeezed 876' w/600 sxs. TOC 300'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2009 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 1345' - solid bottom.
Quality Oil Well Cementing pumped 200 sxs 60/40 pozmix - 4% gel neat - followed with 160 sxs 60/40 pozmix - 4% gel with 500# hulls.
Pulled to 743' - pumped 35 sxs cwc.
PTOH. Squeezed 5 1/2" casing with 40 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Hooked up to backside - pumped 10 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Note: Unknown depth of tubing below 1345'. Last MIT showed tubing at 3111' with AD-1 Packer.

Perfs:

Top	Bot	Thru	Comments
3130	3350		

W.C. OIL
DATE: 7-13-09
NO TO 2010 060023

RECEIVED
MAY 27 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

PKT

MAY 26 2009

ATLANTIC REFINING CO

#4

McCLAY

Arb

12-9-17W

APP N2 N2 SW

Contr.

ROOKS

County

E. 2036

Comm.

11-6-48

Comp.

12-31-48

IP

341 BOPC

PHY POT

Tops	Depth	Datum
HEEB	3109	-1073
LANS	3151	-1115
ARB	3132	-1396
T.O.	3136	-1400

Casing:

10" 191 PERF 24 S, 3432-36
 5" 3433 ACID 1000
 SWB 10 BOFH

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS
