

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20312-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 23-14S-11W
2310 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HINES Well #: 1
County: RUSSELL Total Vertical Depth: 2906 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	289	0	w/170 sxs cmt
PROD	4.5	2249	0	w/150 sxs cmt

94.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2009 10:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUELER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 1350' - 520' - 262'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2009 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2127' - pumped 30 sxs cement - followed with 70 sxs cement with 150# hulls.
Pulled tubing to 600' - pumped 40 sxs cement - cement circulated out of the casing head.
Shut casing in - pumped 35 sxs down tubing and out the braden head.
Pulled tubing out of the well and filled casing with 3 sxs cement.

Perfs:

AVO GLO
MAY 17 7-13-09
BY NO. 2010060027

RECEIVED
MAY 27 2009
KCC WICHITA

Remarks: QUALITY CEMENTING COMPANY-TICKET #3117.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

CM
PKT

Form CP-2/3

MAY 20 2009

SALINE BASIN PETROLEUM CO.
SALINA, KS.

#. H-30 DRLG. COMPANY

Contr. H-30 DRLG. COMPANY

Cty. RUSSELL

Geol. HAP PRYOR

Pool WC

E. 1583 KB Cm. 4/11/69 Cp. 7/17/69

IP PMP 96 BOPD +, %
WTR + 240,000 CFGPD
(GR 39) TARK 2101-
04

API 15-167-20, 312

SMPTops Depth Datum Csg.

SMPTops	Depth	Datum
ANH	505	+1178
GR H	2085	- 403
TARK	2100	- 417
TOP	2447	- 764
BR LM	2789	-1106
LANS	2807	-1124
TD	2906	-1223

8-5/8" 239/170 SX
4 1/2" 2249/150 SX

DST 2887-2905/1', 120' W, BHP
790-750#/50", FP 0-0#

PF 12/2101-04, SO NAT, 100 MA,
SWB LD & SWB 3 BOPH/3 HRS, TRAC
10,000# SD X 10,000 GAL WTR,
SWB PT LD & SWB 5 BOPH, GR 40,

NO LOG
NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS