

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-209-19018'-00-00  
NWNWNW Sec/Twp/Rge 35-10S-23E  
4994 feet from south section line  
4999 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: STATE OF KANSAS FEE FUNDS  
Name & \_\_\_\_\_  
Address \_\_\_\_\_  
AB oil well \_\_\_\_\_ Gas Well XXXXXXX SWD Well/ Input Well \_\_\_\_\_

Lease/Well# CLARKE OW#01  
County WYANDOTTE  
Well Total Depth 600 feet  
Production Pipe: 2 7/8" Size Feet NA  
Surface Casing: 8 5/8" Size Feet NA  
D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE LLC Lic. # 33749

Address: 19245 FORD ROAD CHANUTE KANSAS 66720

Company to plug at: Hour: 11:30 AM Day: \_\_\_\_\_ 16 Month: AUGUST 2006

Plugging proposal received from: JIM KEPLEY

Company Name: KEPLEY WELL SERVICE LLC Phone: 620-431-9212

Were: FILL INSIDE AND OUTSIDE OF PRODUCTION CASING WITH CEMENT FROM BOTTOM TO SURFACE.

Plugging Proposal Received by: TAYLOR HERMAN

TECHNICIAN

Plugging attended by Agent: All XXXXXXX Part \_\_\_\_\_

None \_\_\_\_\_

Operations Completed: Hour: 3:00 PM Day: \_\_\_\_\_ 16 Month: AUGUST 2006

Actual Plugging Report: RAN 1" INSIDE OF 2" CASING AND WASHED DOWN TO 600' THEN RAN 1" ON THE OUTSIDE OF 2" CASING AND WASHED DOWN TO 375'. PUMPED CEMENT ON OUTSIDE FRC 375' TO SURFACE AND PULLED 1" PIPE. PUMPED CEMENT ON INSIDE FROM 600' TO SURFACE AND PULLED 1" PIPE. LET CEMENT FALL BACK AND THEN TOPPED OFF TO SURFACE. A TOTAL OF 140 SACKS OF CEMENT WAS USED. AFTER CEMENTING THE PIPE WAS CUT OFF 6' BELOW SURFACE.

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 07 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Taylor C. Herman  
TECHNICIAN

*PKT*