

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20218-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 33-15S-8W
2998 feet from S Section Line, 2391 feet from E Section Line
Lease Name: MARGARET MUNCIE Well #: 1
County: ELLSWORTH Total Vertical Depth: 2995 feet

Operator License No.: ~~100101~~ KCC Fee Fwd
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	210		
T1	2.5	2600		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/18/2009 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed
Plugging
Method:

SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2009 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU ON 6-17-2009. ENCOUNTERED OBSTRUCTION AT 470'. PUMPED THRU WITH TANK TRUCK. WELL WENT ON VACUUM. TAG BOTTOM AT 2440'. PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. LET SET OVERNIGHT AND TAGGED CEMENT TOP ON 6-18-2009 AT 1900'. PERFORATE AT 901' AND PUMP 20 SX'S CEMENT WITH CALCIUM CHROLIDE. LET SET FOR ALMOST 2 HRS AND TAGGED CEMENT TOP AT 730'. PERFORATE AT 600' AND PUMP 20 SX'S CEMENT WITH CALCIUM CHLROIDE. LET SET FOR APPROX 1.5 HRS. PERFORATE AT 260' AND CIRCULATE 120 SX'S CEMENT TO SURFACE. USED 195 SX'S CEMENT TOTAL. NOTE: THE 2 1/2 TUBING WAS FOUND ORANGE PEELED TO THE 8 5/8" SURFACE. A WINDOW WAS CUT IN THE 8 5/8" & QUALITY WAS ABLE TO GET DOWN BACKSIDE 400'. QUALITY WAS ABLE TO GET PAST ROUGH SPOT INSIDE TUBING AT 470' AND GET DOWN TO 2440'. A SLIM PERFORATING GUN WAS USED TO PERFORATE THE TUBING, THAT WAS USED AS THE PRODUCTION STRING. NO OTHER CASING WAS IN THE HOLE.

Perfs:

KANSAS CORPORATION COMMISSION
JUL - 7 2009
RECEIVED

Control #: 20090075001 (Per Abandoned Well Database)

Remarks: 60-40 POZ, 4% GEL. LOG TECH TICKET #27798. QUALITY TICKET #2317.
Plugged through: TBG

District: 02 Signed Virgil Clothier
(TECHNICIAN)

[Handwritten mark]

[Handwritten mark]