

15-167-22278-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167 - 22,278

N $\frac{1}{2}$ NW SW, Sec. 4, T 12 S, R 12 W/X

2310 feet from N/S section line

790 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Schneider Well # 1

Operator: Ladd Petroleum
Name & P.O. BOX 520
Address Great Bend, Ks. 67530

County Russell

Well Total Depth 3410 feet 110.82

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 $\frac{5}{8}$ feet 380

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Tag Number 79

Plugging Contractor Red Tiger Drilling License Number 5302

Address 1720 Ks. State Bank Building, Wichita, Kansas 67202

Company to plug at: Hour: 6:00 A.M. Day: 3 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Walt Oden

(company name) Red Tiger Drilling (phone) (316) 263-2371

were: _____

8 $\frac{5}{8}$ " 380' S.P. CUC with 225 sks. common 2% Gel - 3% Ca. Cl. (by Buie Cmt) order 160
sks, 50/50 poz mix 4% Gel - 3% ca cl. - 1 sk cello flake and 8 $\frac{5}{8}$ " plug spot with
drill stem - turn hole over - heavy mud between all plugs. no circulation problems,
No show or blow - Elev. 1709' - Anh. 696

~~Did not penetrate ar buckle~~

Signed Marian Schmidt
(DOIC) (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 A.M. Day: 3 Month: February Year: 19 84

ACTUAL PLUGGING REPORT Order 160 sks, 50/50 Poz Mix 4% Gel - 3% Ca cl. and 1 sk cello
flake and 8 $\frac{5}{8}$ " plug spotted with drill stem-turned hole over, heavy mud between all
plugs. 1st plug @ 720' w/20 sks. cmt

2nd plug @ 600' w/80 sks. cmt w/1 sk. Cello flake

3rd plug @ 240' w/40 sks. cmt

4th plug solid bridge hulls - plug @ 40' w/10 sks. cmt.

10 sks. in Rat Hole (Circulate)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED

DATE 2-13-84

INV. NO. 0230

2-3

RECEIVED
STATE CORPORATION COMMISSION

2-13-1984
FEB 13 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed Marian Schmidt
(DOIC) (TECHNICIAN)