

15-167-22228-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22,228 ✓

JE-SE-SE, Sec. 8, T 12 S, R 12 W/E

330 feet from N S section line

330 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5184

Lease Name SHIROKY Well # "A"-1

Operator: SHIELDS OIL PRODUCERS INC.
Name & Address

County RUSSELL

SHIELDS BLDG.
RUSSELL, KANS. 67665

Well Total Depth 3275 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 432

\$106.44

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor SHIELDS DRILG. CO. INC. License Number 2655

Address SHIELDS BLDG. RUSSELL, KANS.

Company to plug at: Hour: 7:00 PM Day: 2 ND Month: NOV Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO BURTON BERRY

(company name) SHIELDS DRILG. INC (phone) 913-483-3141

were: 8 5/8" - 432 FT DR. CUL #1335 5/8" 60/40 QUICKSET. (BY ALLIED OMT.)

ORDER 170 5/8" 50/20 FORMIX 4% GEL-3% CA-CL. AND 8 5/8" Plug.

SPOT WITH DRILL STEM - TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS

~~K-C WELC~~ NO ARBUCKLE, ELEV 1732, ANHY. 416

Signed Margaret Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 PM Day: 2 ND Month: NOV Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 170 5/8" 50/20 FORMIX 4% GEL-3% CA-CL. AND 8 5/8" Plug

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN PLUGS

1st Plug @ 720 FT #20 5/8" OMT., 2nd Plug @ 570 FT #80 5/8" OMT.

3rd Plug @ 240 FT #40 5/8" OMT., 4th Plug SAND BRIDGE HALL'S - Plug @ 40 FT #100 5/8" OMT.

10 5/8" RAT HOLE, (OIC) 10 5/8" MOUSE HOLE (OIC) (CEMENTED BY ALLIED)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 11-21-83

INV. NO. 2017-W

RECEIVED STATE CORPORATION COMMISSION

NOV 10 1983
11-10-1983
CONSERVATION DIVISION
Wichita, Kansas

Margaret Schmidt
(TECHNICIAN)

FORM CP-2/3
3 Rev. 9-82