

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5010  
Name: Knighton Oil Company, Inc.  
Address 1: 1700 N. waterfront Parkway, Bldg. 100-A  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67206 + \_\_\_\_\_  
Contact Person: Earl M. Knighton, Jr  
Phone: (316) 630-9905  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Simpson Depth to Top: 1839 Bottom: 1842 T.D. 1943  
Penn sand Depth to Top: 1680 Bottom: 1686 T.D. 1750  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 127-010010000  
Spot Description: \_\_\_\_\_  
S SW NE SE Sec. 35 Twp. 15 S. R. 7  East  West  
1,650 Feet from  North /  South Line of Section  
990 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Morris  
Lease Name: Trowbridge OWWO Well #: 3  
Date Well Completed: 5/2/1996  
The plugging proposal was approved on: 5/20/09 (Date)  
by: Greg Eves (KCC District Agent's Name)  
Plugging Commenced: 5/20/09  
Plugging Completed: 5/21/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	202'	None
		Production	5 1/2"	1943	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf-Tech: Set 5 1/2" Alpha M-2 CIBP at 1630'. Glass bottom dump bailer run, 2 sacks cement on plug at 1630'. Perforated to plug well, 2 holes at 250'.  
Consolidated: Safety meeting, rig up, break circulation, pumped 94 sacks 60/40 poz, 4% gel down 5 1/2" casing, cement circulated around backside from 250' to surface. Cement circulated in the cellar.  
Wash up and rig down.

RECEIVED

MAY 29 2009

KCC WICHITA

Plugging Contractor License #: 34016 5010 Name: Ruf Nek Well Service & Supply  
Address 1: P.O. Box 1580 Address 2: \_\_\_\_\_  
City: Lincolnvile State: KS Zip: 66858 + 0159  
Phone: (620) 942-5717  
Name of Party Responsible for Plugging Fees: Knighton Oil Company, Inc.  
State of Kansas County, Sedgwick, ss.  
David D. Montague  Employee of Operator or  Operator on above-described well,  
(Print Name)  
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: \_\_\_\_\_

PKT

# Perf-Tech

Wireline Services, Inc.

P.O. Box 87  
 HAYS, KS 67601-0087  
 (785) 623-3969

*Consolidated*

## Invoice

DATE	INVOICE #
5/21/2009	6543

BILL TO

Knighton Oil Co.  
 P.O. Box 1580  
 Hays Kansas 67601

SERVICE DATE	DESCRIPTION	ITEM	AMOUNT
5/20/2009	Trowbridge OWWO # 3 Morris County Kansas  Set 5 1/2" Alpha M-2 CIBP at 1630' Glass bottom dump bailer run, 2 sx cement on plug at 1630' Perforated to plug well. 2 holes at 250'	PERF	1,350.00T
	Truck Rental Sales Tax	Truck set up	400.00T 92.75

RECEIVED  
 MAY 29 2009  
 KCC WICHITA

*TROWBRIDGE #3  
 SET PLUG &  
 PERFORATE  
 PLUGGING*

Price reflects discount Thank You for your business!!	<b>Total</b>	\$1,842.75
--	--------------	------------

WELL FILE





**CONSOLIDATED**  
Oil Well Services, LLC

**ENTERED**

TICKET NUMBER 20927  
LOCATION El Dorado #80  
FOREMAN Jim Thomas

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
5-21-09	4495	Leeds #1, Trowbridge #3				Monro																
CUSTOMER Kighton Oil Co			<table border="1"> <thead> <tr> <th>TRUCK #</th> <th>DRIVER</th> <th>TRUCK #</th> <th>DRIVER</th> </tr> </thead> <tbody> <tr> <td></td> <td>Greg Jerdal</td> <td>290</td> <td></td> </tr> <tr> <td></td> <td>John</td> <td>434</td> <td></td> </tr> <tr> <td></td> <td></td> <td>439</td> <td></td> </tr> </tbody> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER		Greg Jerdal	290			John	434				439	
TRUCK #	DRIVER	TRUCK #					DRIVER															
	Greg Jerdal	290																				
	John	434																				
		439																				
MAILING ADDRESS 221 S. Broadway Suite 710																						
CITY Wichita	STATE KS	ZIP CODE 67202																				

JOB TYPE Plug HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 4 1/2", 5 1/2"  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety Meeting Rm up to 4 1/2" Break circulation, Pump 100 sks 60/40 poz 4% gel. Circulated from 250g. "Perf" around backside in the cellar. 2nd Well Pumped 94 sks 60/40 poz 4% gel down 5 1/2" casing cement circulated around backside from 250g. to surface. Cement circulated in the cellar. Wash up & rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	590.00	590.00
5406	55	MILEAGE	3.45	189.75
5405A	2nd	Well charge	400.00	400.00
1131	194 sks	60/40 poz	10.70	2075.80
113A	800 lbs	gel	.16	128.00
5502C	8 hrs	80 BDh Vac Truck	94.00	752.00
5407A	10.0 Tons	55 miles Bulk Del.	1.16	638.00
<b>RECEIVED</b>				
<b>MAY 29 2009</b>				
<b>KCS WICHITA</b>				
<b>Subtotal</b>				<b>4773.55</b>
SALES TAX				138.84
ESTIMATED TOTAL				4912.39

Ravin 3737 AUTHORIZATION [Signature] TITLE 829718 DATE 5-21-09



**CONSOLIDATED**  
Oil Well Services, LLC

**REMIT TO**  
Consolidated Oil Well Services, LLC  
Dept. 970  
P.O. Box 4346  
Houston, TX 77210-4346

MAIN OFFICE  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE

Invoice # 229718

Invoice Date: 05/26/2009 Terms:

Page 1

KNIGHTON OIL CO  
BUILDING 100 SUITE A  
1700 N. WATERFRON PARKWAY  
WICHITA KS 67206  
(316) 264-7918

LEEDS #1, TROWBRIDGE #X3  
20927  
05-21-09

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	194.00	10.7000	2075.80
1118A	S-5 GEL/ BENTONITE (50#)	800.00	.1600	128.00

  

Description	Hours	Unit Price	Total
290 P & A OLD WELL	1.00	590.00	590.00
290 EQUIPMENT MILEAGE (ONE WAY)	55.00	3.45	189.75
290 P & A OLD WELL	1.00	400.00	400.00
434 80 BBL VACUUM TRUCK (CEMENT)	8.00	94.00	752.00
439 TON MILEAGE DELIVERY	550.00	1.16	638.00

RECEIVED

MAY 29 2009

KCC WICHITA

Parts: 2203.80 Freight: .00 Tax: 138.84 AR 4912.39  
Labor: .00 Misc: .00 Total: 4912.39  
Sublt: .00 Supplies: .00 Change: .00

Signed \_\_\_\_\_

Date \_\_\_\_\_

BARTLESVILLE, OK  
918/338-0808

ELDORADO, KS  
316/322-7022

EUREKA, KS  
620/583-7664

GILLETTE, WY  
307/686-4914

McALESTER, OK  
918/426-7667

OTTAWA, KS  
785/242-4044

THAYER, KS  
620/839-5269

WORLAND, WY  
307/347-4577