

15-167-22228-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Russell County. Sec. 8 Twp. 12 Rge. 12 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

SE SE SE

Lease Owner Shields Oil Producers, Inc.

Lease Name Shiroky "A" Well No. 1

Office Address Shields Bldg., Russell, Kansas 67665

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 11-2 1983

Application for plugging filed " 1983

Application for plugging approved " 1983

Plugging commenced " 1983

Plugging completed " 1983

Reason for abandonment of well or producing formation

Dry hole


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation Depth to top Bottom Total Depth of Well 3,275

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	432'	Cmtd w/335 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Spotted 20 sax cement @3,270' thru 4 1/2" drill pipe
- Fill hole w/heavy mud
- Push bridge plug to 720', spotted 20 sax cement on plug thru 4 1/2" drill pipe
- Push bridge plug to 570', spotted 80 sax cement on plug thru 4 1/2" drill pipe
- Push bridge plug to 240', spotted 40 sax cement on plug thru 4 1/2" drill pipe
- Push bridge plug to 40' w/ 1/2 sax hulls on plug
- Dump 10 sax cement on plug to cellar
- Dump 10 sax cement in rat hole
- Dump 10 sax cement in mouse hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.

STATE OF Kansas COUNTY OF Russell, ss.  
R. L. Shields (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

*R. L. Shields*

Shields Bldg., Russell, Kansas 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1983

*Kenneth D. Dole*

Notary Public.

My commission expires

**KENNETH D. DOLE**

NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Expires April 17, 1985

RECEIVED  
STATE CORPORATION COMMISSION  
11-18-1983  
NOV 18 1983

CONSERVATION DIVISION  
Wichita, Kansas