

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-8380 Operator License #: 4549

Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 05/14/2009 (Date)

by: Eric Maclaren (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Chase Depth to Top: 2595 Bottom: 2675 T.D. 2707

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15- 175-00357-00-00

Lease Name: Liberal

Well Number: 1-32 KCC PKT per CP213

Spot Location (QQQQ): NW - NE - NE - NE

251 Feet from  North /  South Section Line

360 Feet from  East /  West Section Line

Sec. 32 Twp. 34 S. R. 33  East  West

County: Seward

Date Well Completed: 06/12/1959

Plugging Commenced: 05/14/2009

Plugging Completed: 05/19/2009

KCC PKT  
per GPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled out
		0	706'	7"	706'	0
		0	2704'	4-1/2"	2704'	918'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

Pull 2-3/8" tbq. Mixed 300 lbs hulls & 20 sks cmt; pump plug from 2595' to 2335'. Pump mud spacer to 1600'.  
Mix 20 sks cmt & plug from 1600' to 1340'. Shot 4.5" csg loose @ 918' & pulled to 740'. Circ. mud, mix  
100 sks cmt & pump from 740' to 240'. Pull 4.5" csg. Tag plug @ 430'. Ran 4.5" to 430'. Mixed 80 sks cmt &  
plug from 430' to 30'. Pull 4.5" csg to 30'. Mix 10 sks cmt & plug 30'-0' Cut & cap 7" csg 4' below grd level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151

Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.


Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 29th day of May, 2009

Bertha Neff My Commission Expires: 12-27-09  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

JUN 01 2009

KCC WICHITA

PT