


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 11 Twp. 12S Rge. (E) 15 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Sec SE/4  
Lease Owner. Stearns Petroleum, Incorporated  
Lease Name. W. Foster Well No. 1  
Office Address. Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed. June 11 19 48  
Application for plugging filed. June 11 19 48  
Application for plugging approved. June 11 19 48  
Plugging commenced. June 18 19 48  
Plugging completed. June 25 19 48  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production. 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? ~~MISSOURI~~ ~~KANSAS~~ Yes

Name of Conservation Agent who supervised plugging of this well. M. A. Rives, Hays, Kansas  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3293 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4	202	none
				7	2950	900
				5-1/2	3055	2994
				4-1/2	319	319

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 3293 feet to 2940 feet  
Bridge set at 2940 feet  
six sacks of cement set at 2940 feet in 7" casing  
Mud 2900 feet to 200 feet  
Bridge at 200 feet. Run twenty sacks of cement.  
Mud 200 feet to 20 feet  
Bridge at 20 feet  
Cement from 20 feet to bottom of cellar

Surface casing 10-3/4" set at 202 feet and cemented from bottom to top with 100 sacks of cement

6-28-1948


(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to STEARNS PETROLEUM, INCORPORATED  
Address Box 313, Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.  
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Russell, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 48  
My commission expires August 17, 1950



Notary Public.

15-167-00438-00-00

FOSTER #1 WELL LOG

STEARNS PETROLEUM, INCORPORATED  
Commenced: April 26, 1948  
Completed: June 11, 1948

SEc SE/4 Section 11-12S-15W  
Russell County, Kansas.  
Elevation: 1763'

	FROM	TO
Rock-shale and shells	0	30
Shells and shale	30	110
Sand	110	205
Shale and shells	172	205
202' of 10-3/4" casing set and cemented with 100 sax of cement		
Shale and shells	205	413
Iron and shale	413	443
Iron-shale and shells	443	540
Red Rock	540	646
Shale and shells	646	850
Hard sand	850	865
Sand and shale	865	1005
Sandy shale	1005	1228
Shale and salt	1228	1490
Sandy shale	1490	1615
Sandy shale and lime	1615	1721
Shale and lime	1721	2949
Kansas City lime	2949	2955
7" casing set at 2950' cemented with 40 sax of cement		
Lime	2955	2963
Shale	2963	2970
Lime and shells	2970	2981
Lime	2981	3009
Shale	3009	3012
Lime	3012	3019
Soft lime	3019	3026
Hard lime	3026	3045
Lime	3045	3104
Shale	3104	3106
Lime	3106	3117
Red shale	3117	3121
Hard lime	3121	3125
Blue shale	3125	3130
Lime	3130	3146
Black shale	3146	3148
Hard lime	3148	3151
Lime	3151	3154
Shale	3154	3155
Lime and shells	3155	3162
Lime	3162	3177
Hard lime	3177	3182
Lime	3182	3204
Gray shale	3204	3209
Lime	3209	3219
Red shale	3219	3221
Soft lime	3221	3226
Lime	3226	3230
Soft lime	3220	3232
Hard lime	3232	3234
Lime	3234	3238
Red shale	3238	3240
Conglomerate	3240	3251
Lime	3251	3266
Green shale	3266	3268
Lime	3268	3291
Granite	3291	3293

TOTAL DEPTH 3293'

STATE OF KANSAS )  
COUNTY OF RUSSELL ) SS

6-28-1948  
JUN 28 1948

I hereby certify that the above information is true and correct to the best of my knowledge.

*O. G. Stearns*

O. G. Stearns

Subscribed and sworn to before me this 26th day of June, 1948.

My Commission expires  
August 17, 1950.

PLUGGING  
JUN 17 1948  
40

*B. F. W. Evers*  
Notary Public