

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

RUSSELL County. Sec. **12** Twp. **12** Rge. **15** (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines **NE, SE, NE**
Lease Owner **JONES, SHELburne & FARMER, INC.**
Lease Name **MELLARD** Well No. **1**
Office Address **RUSSELL, KANSAS**
Character of Well (completed as Oil, Gas or Dry Hole) **DRY HOLE**
Date well completed **11/12/49** 19.
Application for plugging filed **11/11/49** 19.
Application for plugging approved **11/11/49** 19.
Plugging commenced **11/12/49** 19.
Plugging completed **11/12/49** 19.
Reason for abandonment of well or producing formation **DRY**



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production **NEVER PRODUCED** 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? **YES**

Name of Conservation Agent who supervised plugging of this well **MR. PETTY**
Producing formation **NONE** Depth to top Bottom Total Depth of Well **3171** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	209'	None
				Cemented to top		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Hole was filled to bottom with heavy mud.
- Wooden plug pumped to 200' and 20 sacks cement mixed and spotted on top of plug through drill pipe.
- Hole filled to top with heavy mud and 15 sacks cement mixed and dumped in top.
- Metal cap welded over surface casing.

11-14-1949
RECORDED
INDEXED
ST. JAMES
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to **JOHN O. FARMER**
Address **RUSSELL, KANSAS**

STATE OF **KANSAS**, COUNTY OF **RUSSELL**, ss.
John O. Farmer (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *John O. Farmer*
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this **12th** day of **November**, 19**49**

My commission expires **June 3, 1953**
Phyllis Bethany
Notary Public.



Jones, Shelburne & Farmer, Inc.

Russell, Kansas

15-167-00379-00-00
CONTRACTOR'S VERIFIED LOG

Operator JONES, SHELBURNE & FARMER Farm Name MELLARD Well No. 1
 Location C/NE SE NE SECTION 12-12-15
 Pool Name WILDCAT County RUSSELL State KANSAS
 Commencement Date 10/30/49 Completion Date 11/11/49

Log of Well

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
0	130	Sand and Soil		
130	200	Shale and Shells		
200	282	Sand		
282	410	Iron and Pyrite		
410	710	Shale and Shells		
710	760	Anhydrite		
760	1080	Shale and Shells		
1080	1330	Shale, Salt and Shells		
1330	1415	Shale and Shells		
1415	2860	Lime and Shale		
2860	2965	Lime		
2965	2967	Lime and Shale		
2967	3171	Lime		
	3171	Total Depth (DRY & ABANDONED)		
<p>TOPS</p> <p>710 Anhydrite 2502 Topeka 2755 Heebner 2775 Toronto 2806 Lansing K. G. 3136 Arbuckle</p> <p>209' of 8 5/8" Surface Pipe</p>				

PLUGGING

WELL SEC 18 T 18 R 15W

BOOK PAGE 124 LINE 5

RECEIVED

NOV 14 1949
 STATION
 SECTION

(Well Log Continued)

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
			Total Depth	

Was well to be deepened by another Contractor? _____

CASING LEFT IN HOLE AFTER COMPLETION OR ABANDONMENT

Size	Wt.	Grade	Range	Thread	FOOTAGE						
					Delivered	Run	Set At	Unused	Pulled	Left in Hole	

<p>Deviation From Vertical Data Is Correct as Shown</p> <p>_____ Company Superintendent</p> <p>(This space for Company use)</p>

The foregoing Well Log and other data are correct.

—JONES, SHELBURNE & FARMER, Inc.
Contractor

By John O. Farmer